BANGALORE DIVISION.

Dated 28th November 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 16th December 1929, for extending the 5th and 6th Pavilion of Victoria Hospital, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th September 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3a. Tenders quoting percentages below or above estimate will not be accepted.

4. Each tender must be accompanied by a deposit of Rs. 1,500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending 5th and 6th Pavilion of Victoria Hospital, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract of quantities for extending 5th pavilion.

No.	Items of work	Per	Quantity	Rate
1	Earthwork excavation foundation and filling in basement.	C.yds.	200	
2	Concrete with mortar do ..	C.ft.	1,078	
3	Burnt stone in clay foundation ...	,,	4,066	
4	Burnt stone in clay superstructure	,,	4,504	
5	Burnt stone in mortar arch work with key stones ..	,,	161	
6	Burnt stone slabs 6" thick	S.ft.	463	
7	Teakwood doors ½ panelled and half glazed as per *6th pavilion complete.*	,,	188	
8	Teakwood windows outside panelled and inside glazed with iron fittings and iron bars, etc.	,,	100	
9	Removing and refixing windows.	,,	20	
10	Teakwood windows venitioned and glazed ...	,,	175	
11	Steel trusses as per plan	Cwt.	27½	
12	Teakwood work drought and put up ...	C.ft.	214.50	
13	Roofing with 1st Class Mangalore tiles of Basel Mission.	Sqr.	18·30	

No.	Items of work	Per	Quantity	Rate
14	Teakwood ceiling to roof	,,	18·30	
15	Ridge tiles set in mortar	R.ft.	61	
16	Pucca terrace floor 9″ thick complete ...	Sqr.	11·16	
17	Cornice work 12″ thick	R.ft.	139	
18	Parapet wall 2′ height	,,	136	
19	Plastering with mortar	Sqr.	41·00	
20	Pointing with mortar	,,	39·00	
21	Silicate painting 3 coats	,,	10·00	
22	Dadoo painting to walls	,,	6·25	
23	Glazed tiles to walls fixed with cement ...	,,	6·73	
24	Cornice glass tiles	R ft.	141	
25	Flooring with marcellas tiles on 3″ concrete bed and cement pointing.	Sqr.	16·60	
26	Flooring with 1½″ thick cuddapah slabs do ...	,,	4·58	
27	Constructing V shaped drains alround the building with side slabs.	R.ft.	170	
28	Teakwood ornamental eave board ...	,,	152	
29	Teakwood finials	Each	1	
30	Teakwood pendants	,,	4	
31	Dismantling and removing the existing building as per 6th pavilion.	Lump	sum	
32	Filling earth to basement and consolidation ...	C.yd.	160	
33	Cornice work with stone slabs 3 sides of arch way pillars.	R.ft.	42	

Abstract of quantities for extending 6th pavilion.

1	Dismantling and removing the existing stone masonry wall.	C.ft.	697
2	Removing the existing glass tiles and stacking ...	Sqr.	2·70
3	Dismantling and removing the existing pucca terrace, flate with joists, etc., complete.	,,	1·61
4	Dismantling the existing parapet wall and removing the debris, etc.	R.ft.	36
5	Removing and stacking the existing ventilators ...	Each	7
	Extending.		
6	Earthwork excavation foundation and filling in basement.	C.yd.	179
7	Burnt stone jelly concrete in mortar ...	C.ft.	948
8	Burnt stone in clay foundation	,,	3,584
9	Burnt stone clay in superstructure	,,	4,014
10	Burnt stone in mortar, arch work with key stone dressed.	,,	76
11	Teakwood doors ½ panelled and ½ glassed shutters with iron fittings and 1½″ thick plank, etc.,	S.ft.	188
12	Teakwood window, outside panel and inside glassed shutters with ¾″ iron bars and iron fittings and 1″ thick plank, etc.	,,	60
13	Removing and refixing the existing window ...	,,	20
14	Teakwood windows outside ventioned and inside glassed with ¾″ iron bars and iron fittings and 1″ thick plank etc.	,,	175
15	Steel trusses 21ft. span as per Marryots specification	C.ft.	371½

No.	Items of work	Per	Quantity	Rate
	Extending—concld.			
16	Teakwood work wrought and put with wood-oiling, etc.	C.ft	195·42	
17	Roofing with 1st class Mangalore tiles of Basel Mission on 2" x 1" teak reepers, etc., complete.	Sqr.	18·30	
18	Teakwood ceiling to roof	,,	18·30	
19	Ridge tiles set in a mortar	R.ft.	61	
20	Pucca terrace roof flat 9" thick, complete ..	Sqr.	9·59	
21	Cornice work 12" deep	R.ft.	113	
22	Parapet wall 2' height	,,	119	
23	Plastering with mortar	Sqr.	41·00	
24	Pointing with mortar	,,	34·00	
25	Silicate painting 3 coats	,,	14·00	
26	Dadoo painting to walls	,,	6·26	
27	Glass tiles to wall fixed with cement	,,	6·75	
28	Cornice glass tiles	R.ft.	141	
29	Flooring with Marcellis tiles on 3" concerete bed and cement pointing.	Sqr.	16·60	
30	Flooring with 1½" thick Cuddapah slabs on 3" concrete bed and cement pointing.	,,	3·26	
31	Constructing cement drain and latrine seats, etc. ...	Lump	sum	
32	Flooring with 1½" thick Cuddapah slabs alround the building to ground level.	Sqr.	4·35	
33	Constructing V shaped drains alround the building with side slabs on top, etc.	R.ft.	150	
34	Burnt stone slabs 6" thick roughly dressed and set in mortor, etc.	S.ft.	424	
35	Filling the available excavation earth to basement level with forming watering and tamping, etc.	C.yds.	148	
36	Teadwood eve board ornamental	R.ft.	152	
37	Teakwood finials	Each	1	
38	Teakwood pendants	,,	4	
39	Cornice work with stone slabs of arch ways of pilliars.	R.ft.	30	
	Proposed New Verandah alround the Electric Cardeograph.			
1	Earthwork excavation foundation and filling in basement level	C.yds.	52	
2	Concrete with mortar	C.ft.	278	
3	Burnt stone in clay foundation	,,	995	
4	Burnt stone in clay superstructure	,,	447	
5	Burnt stone in mortar arch work with key stones ...	,,	184	
6	Burnt stone slabs 6" thick	S.ft.	158	
7	Teakwood work wrought and put up with wood oiling, etc.	C.ft.	58·31	
8	Pucca terrace flat 9" thick	Sqr.	4·89	
9	Parapet wall 2' height	R.ft.	69	
10	Flooring with 1½' thick Cuddapah slabs on 3" concrete bed and cement pointing.	Sqr.	4·04	
11	Pointing with mortar	,,	15·00	
12	Cornice work 12" deep	R.ft.	73	
13	Cornice work for pillars 3 sides moulding with stone slabs.	,,	41	

Dated 2nd December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 16th December 1929, for constructing dry stone revetment to the storm drain in Kitchatty Chattram Road, etc., removing and refixing stone ware pipe drain in the compound of the Central Jail Extension, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3 A. Tenders quoting percentage below or above estimate will not be accepted.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing drain dry stone revetment to the storm water drain and removing and refixing stoneware drain in the compound of Central Jail, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing dry stone revetment to the storm water drain in Kitchetty Chattram Road from Central College Hostel Compound to road by the side of Mr. C. V. Narasimha Iyengar's House.

No.	Items of work	Per	Quantity	Cost
				Rs.
1	Earthwork excavation	C.ft.	649	
2	Constructing dry stone revetment with size burnt stones...	,,	12,389	
3	Burnt stone in chunnam masonry	,,	960	
4	Burnt stone slabs 6" thick for covering	S.ft.	400	
	Removing and refixing existing 6" stoneware pipe drain in the Compound of Central Jail Extension, Bangalore.			
1	Removing existing 6" stoneware pipe full ...	R.ft.	514	
2	Dismantling manholes	Each	4	
3	Earthwork excavation for new pipe line including the earth filling.	Cyd.	231	
4	Relaying 6" old pipe and new pipe with jointing with rope and cement.	R.ft.	809	
5	6" new stoneware pipe for pipe line	,,	398	
6	Manholes 3' feet deep	Each	5	
7	Do 4' feet deep	,,	1	

H. R. VENKATASUBBA RAO,
Executive Engineer.

IN THE COURT OF THE MUNSIFF AT KOLAR GOLD FIELDS.

Insolvency Application No. 51 *of* 1929-30.

Thambusamy Pillay, son of Veerasamy Pillay, Cook, Kolar Gold Fields Officers' Club, Ooregaum ... ... ***Petitioner.***

vs.

(1) Jamadar Seenappa and Krishnappa by agent Ramaswamiah, Money-lender, Robertsonpet, (2) Gazamall Chunilal, Money-lender, Robertsonpet ... ... ***Opponents.***

Whereas the said petitioner has applied to this Court by a petition, dated 21st day of October 1929, to be declared an insolvent under the Mysore Insolvency Regulation, VI of 1911, and your names appear in the list of creditors, filed by the aforesaid debtor, this is to give you notice that the Court has fixed the 17th day of December 1929, for the hearing of the aforesaid petition and the examination of the debtor. If you desire to be represented in the matter you should attend in person or by duly instructed pleader.